

01 FRONT ELEVATION



02 REAR ELEVATION



03 LEFT SIDE ELEVATION

PLANS REQUIRE
HEALTH DEPT. APPROVAL
CALL (912) 356-2160
FOR INFORMATION

The building official may revoke a permit or approval issued under the provisions of this code in cases of any false statement or misrepresentation of fact in the application or on the plans on which the permit or approval was based. (Sec. 112.6)



04 RIGHT SIDE ELEVATION

FIRE STOPPING REQUIREMENT

Penetrations thru rated walls and floors shall be sealed with a material capable of preventing the passage of flames and hot gases when subjected to the requirements of the Test Standard specific for Fire Stops ASTM E-814.

A COMPLETE SET OF APPROVED PLANS AND SPECIFICATIONS SHALL BE MAINTAINED ON THE CONSTRUCTION SITE.

POST BUILDING PERMIT ON SITE AT ALL TIMES
By Order
DEPARTMENT OF INSPECTIONS



07 SITE PLAN
NO SCALE



06 VICINITY MAP
NO SCALE



REFER TO PAINT SCHEDULE FOR PAINT SPECIFICATIONS AND COLOR

05 TYPICAL EXTERIOR CHECKERBOARD
SCALE: 3/4" = 1'-0"

GENERAL NOTES:

1. All new interior finishes must carry a One Hour Flame Spread rating.
2. All new glazing shall conform to Safety Glazing requirements of applicable building code.
3. Panic hardware must be provided on all exit doors. All exits must be able to be opened from the inside without use of a key or any special knowledge or effort.
4. Lighted exit signs must be provided at each exterior door and as necessary to direct exit travel.
5. All HVAC is existing and no new HVAC equipment is being added.
6. General Contractor is required to meet with ShowBiz Pizza Time, Inc. technician to review games layout and compressed air requirements.
7. General Contractor is to provide and install gypsum board at any area where wall covering has been removed or surface has been damaged.
8. General Contractor is to match the height of existing doors and field verify door sizes and trim before ordering.
9. General Contractor is responsible for painting coin changers and is to have ShowBiz Pizza Time, Inc. technician install new cover before item is painted.
10. General Contractor to match existing finishes, color and texture when matching existing items.
11. General Contractor is to provide temporary lighting in any area where light fixtures have been removed for operations of next day usage.

INDEX OF DRAWINGS

PROJECT DATA

PROJECT AREA: 10,354 Sq. Ft.
BUILDING CODE: 1985 SBC w/ '86 Revisions

JACK H. MORGAN, CONSULTING ARCHITECT, A.I.A.
B&W
BURSON & WILLIAMS ARCHITECTS INC.

SHOWBIZ PIZZA
APPROVED
PRESIDENT
V.P. CONSTRUCTION
FOR PERMIT & BID
FOR CONSTRUCTION
REVISIONS
#1
#2

SHOWBIZ PIZZA #605 – SAVANNAH
6700 ABERCORN ST. – SAVANNAH, GEORGIA
SHOWBIZ PIZZA TIME, INC.
4441 WEST AIRPORT FREEWAY
IRVING, TEXAS 75062

EXTERIOR ELEVATIONS

Date
08 FEB 1991
Revisions

Project Number
90-500

Sheet Number
A1
of 8

NOTES:

1. WHEN REMOVING PVC PIPE, ALL LINES AND FILL HOLE WITH CONCRETE - PATCH AND FINISH TO MATCH ADJACENT AREAS
2. EXISTING F.S., F.D. AND D.C. TO REMAIN UNLESS NOTED OTHERWISE
3. EXISTING F.E.C. TO REMAIN UNLESS NOTED OTHERWISE
4. REMOVE POWER POLES
5. REMOVE WALL VINYL AND FLOAT OR TEXTURE ALL WALLS BEFORE PAINTING. VERIFY WITH PROJECT MANAGER
6. REMOVE EXISTING CARPET
7. REMOVE COAT RACKS, SIGNS, ETC. AND REINSTALL AFTER PAINTING
8. ALL EXISTING AIR LINES TO REMAIN. RELOCATE IF REQUIRED
9. REMOVE QUARRY TILE UNDER NEW COUNTERS REFER SHEET A3 FOR COUNTER LOCATIONS
10. REMOVE ANY EXISTING WAINSCOTING, PANELING, CARPET, SOUND BOARD, AND TRIM ON WALLS. REPAIR AND REFINISH WALLS
11. REFER TO SHEET A8 FOR DEMOLITION NOTES

KEY

- EXISTING TO REMAIN
- EXISTING TO BE REMOVED
- EXISTING HEADER TO REMAIN



01 DEMOLITION PLAN

SCALE: 3/16" = 1'-0"

OFFICE COPY

BURSON WILLIAMS ARCHITECTS INC.

JACK H. BURSON, CHARLES W. WILLIAMS, A.I.A.

SHOWBIZ PIZZA

APPROVED:

PRESIDENT

V.P. CONSTRUCTION

FOR PERMIT & BID:

FOR CONSTRUCTION:

REVISIONS:

#1

#2

SHOWBIZ PIZZA #605 — SAVANNAH

6700 ABERCORN ST. - SAVANNAH, GEORGIA

SHOWBIZ PIZZA TIME, INC.
4441 WEST AIRPORT FREEWAY
IRVING, TEXAS 75062

DEMOLITION PLAN

Date
08 FEB 1991

Revisions

Project Number
90-500

Sheet Number
A2

of 8



01 NEW CONSTRUCTION FLOOR PLAN

SCALE : 3/16" = 1'-0"

ALTERNATE NO. 1

THE GENERAL CONTRACTOR IS TO PROVIDE AN ITEMIZED LIST OF DEDUCTIONS FOR THE ITEMS LISTED BELOW

1. OMIT THE INSTALLATION ONLY OF THE CADDY CABINET LOCATED BEHIND THE GIFT COUNTER-REFER TO A7/07
2. OMIT THE INSTALLATION ONLY OF ALL DROP BOXES LOCATED BELOW THE ORDER COUNTERS-REFER TO A7/15
3. OMIT THE INSTALLATION ONLY OF ANY COAT RACKS
4. OMIT THE INSTALLATION ONLY OF ANY BOOTH INSERTS INDICATED ON E1/01
5. OMIT THE INSTALLATION OF (1) 1875 WATT 18 AMP 115 VOLT 60 CYCLE DUPLEX OUTLET FOR COFFEE BREWER, AND (1) 1775 WATT 15 AMP SINGLE PHASE DUPLEX OUTLET FOR TEA BREWER-REFER TO E1/01 FOR LOCATIONS
6. OMIT THE INSTALLATION ONLY OF THE DIAPER SHELF-REFER TO A3/01 FOR LOCATION
7. OMIT THE INSTALLATION ONLY OF ALL BOOTHS, TABLES AND BASES AS INDICATED ON E1/01
8. OMIT THE MODIFICATION AND INSTALLATION OF ALL BENCHES-REFER TO A7/03 FOR MODIFICATIONS AND TO E1/01 FOR LOCATION
9. OMIT THE PROVISION AND INSTALLATION OF ALL OUTLETS ABOVE CEILING FOR MECHANICAL-REFER TO E1/01 FOR LOCATIONS
10. OMIT THE INSTALLATION ONLY OF ALL NEW HANGING LIGHTS IN SHOWROOM-REFER TO E2/01 FOR LOCATIONS

NOTES:

INSTALL BEVERAGE AND ORDER DROP BOXES IN NEW ORDER COUNTER

RELOCATE GUEST CHECK HOLDER TO BOTTOM OF PORTION CHART

MOUNT PORTION CHART 1'-0" ABOVE MAKE TABLE

ALL CONDENSATE TO DISCHARGE INTO A FLOOR SINK (VIA A 1" AIR GAP)

EXISTING QUARRY TILE AND 6" SANITARY COVE QUARRY BASE IN KITCHEN AND PREP AREA TO REMAIN

ALL FLOOR SINKS TO BE INSTALLED FLUSH WITH FINISH FLOOR

WHERE FLOOR SINKS ARE REQUIRED USE EXISTING IF POSSIBLE INSTALL NEW OTHERWISE FLOOR SINKS SHOULD BE 1/2 EXPOSED FOR ACCESSIBLE CLEANING

ALL EQUIPMENT SHALL MEET APPLICABLE NATIONAL SANITATION FOUNDATION (NSF) DESIGN AND INSTALLATION REQUIREMENTS OR ITS EQUIVALENT

PROVIDE TRANSITION STRIPS AT ALL CHANGES IN FLOORING MATERIAL

PROVIDE AND INSTALL AT ALL WALL CORNERS CLEAR CORNER GUARDS APPLIED WITH CLEAR SILICONE

ALL EXISTING DOORS TO BE PAINTED REQUIRE SANDING AND FIELD REPAIR OF DAMAGE WITH WOOD PUTTY BEFORE PAINTING

CONTRACTOR TO VERIFY CONDITIONS & DIMENSIONS PRIOR TO CONSTRUCTION

BUFF = MARLITE 3407 "BUFF"
OAK = MARLITE 326-WG2 "NATURAL OAK"

OFFICE COPY

RECEIVED APR 11 1991 DEPT. OF INSPECTIONS

BSW ARCHITECTS INC.

SHOWBIZ PIZZA #605 - SAVANNAH
6700 ABERCORN ST. - SAVANNAH, GEORGIA
SHOWBIZ PIZZA, INC.
4400 WEST AIRPORT FREEWAY
IRVING, TEXAS 75062

NEW CONSTRUCTION FLOOR PLAN

Date
08 FEB 1991

Revisions

Project Number
90-500

Sheet Number
A3
of 8



01 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"



02 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"



03 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"



04 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"



05 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"

OFFICE COPY

RECEIVED APR 11 1991 DEPT. OF INSPECTIONS

BOSWELL WILLIAMS ARCHITECTS INC.

ACR & BOSWELL CONSULTING ARCHITECT, A.I.A.

STATE OF GEORGIA

SHOWBIZ PIZZA

APPROVED

PRESIDENT

V.P. CONSTRUCTION

FOR PERMIT & BID

FOR CONSTRUCTION

REVISIONS

SHOWBIZ PIZZA #605 - SAVANNAH

6700 ABERCORN ST. - SAVANNAH, GEORGIA

SHOWBIZ PIZZA TIME, INC.
4444 WEST AIRPORT FREEWAY
IRVING, TEXAS 75062

INTERIOR ELEVATIONS

Date: 08 FEB 1991

Revisions

Project Number: 90-500

Sheet Number: A4

of 8



01 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"



03 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"



02 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"



04 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"



05 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"



06 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"



07 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"



08 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"



09 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"



10 GIFT COUNTER-FRONT

SCALE: 1/2" = 1'-0"



11 ORDER COUNTER-FRONT

SCALE: 1/2" = 1'-0"



12 GIFT COUNTER-REAR

SCALE: 1/2" = 1'-0"



13 ORDER COUNTER-REAR

SCALE: 1/2" = 1'-0"



14 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"



15 INTERIOR ELEVATION

SCALE: 1/4" = 1'-0"

JACK H. HOWARD, CONSULTING ARCHITECT, A.I.A.
B&W
BURSON & WILLIAMS ARCHITECTS INC.
STATE OF GEORGIA

SHOWBIZ PIZZA

APPROVED:

PRESIDENT

V.P. CONSTRUCTION

FOR PERMIT & BID

FOR CONSTRUCTION

REVISIONS

#1

#2

SHOWBIZ PIZZA #605 – SAVANNAH
6700 ABERCORN ST. – SAVANNAH, GEORGIA

SHOWBIZ PIZZA TIME, INC.
4441 WEST AIRPORT FREEWAY
IRVING, TEXAS 75062

INTERIOR ELEVATIONS

Date
08 FEB 1991

Revisions

Project Number
90-500

Sheet Number
A5
of 8



13 PARTITION SECTION

14 PARTITION SECTION

SCALE: 1 1/2" = 1'-0"



10 DETAIL FOR VESTIBULE WINDOW



06 WINDOW HEAD & SILL DETAIL

JAMB SIMILAR



07 NEW INTERIOR PARTITION

SCALE: 3/4" = 1'-0"

TYPICAL SECTION



15 DROP BOX

SCALE: 1 1/2" = 1'-0"

CEILING BRACING NOTES

1. Four No. 12 gauge wires must be secured to the main runner within 2 inches of the cross runner intersection and splayed 90 degrees from each other at an angle not exceeding 45 degrees from the plane of the ceiling. A strut fastened to the main runner shall be extended to and fastened to the structural members supporting the roof or floor above. The strut shall be adequate to resist the vertical component induced by the bracing wires. These horizontal restraint points shall be placed 12 feet on center in both directions with the first point within 6 feet from each wall. Attachment of the restraint wires to the structure above shall be adequate for the load imposed.
2. Lateral force bracing members shall be spaced a minimum of 6 inches from all horizontal piping or duct work that is not provided with bracing restraints for horizontal forces. Bracing wires shall be attached to the grid and to the structure in such a manner that they can support a design load of not less than 200 pounds or the actual load, whichever is greater, with a safety factor of 2.



08 BEVERAGE BAR SECTION

SCALE: 3/4" = 1'-0"



16 SALAD BAR ELEVATION

SCALE: 1/2" = 1'-0"



11 RECESSED THANK YOU DOOR

SCALE: 3/4" = 1'-0"



17 SUSPENDED CEILING LATERAL TIE

SCALE: 3" = 1'-0"



12 BEVERAGE BAR BACK ELEVATION

SCALE: 1/2" = 1'-0"



09 BEVERAGE BAR COUNTERTOP

SCALE: 1/2" = 1'-0"



01 SECTION @ ORDER COUNTER



02 SECTION @ ORDER COUNTER

SCALE: 1" = 1'-0"



03 SECTION @ ORDER COUNTER

SCALE: 1" = 1'-0"



04 SECTION @ GIFT COUNTER

SCALE: 1" = 1'-0"



05 SECTION @ SALAD BAR

SCALE: 1" = 1'-0"

JACK H. WERNER, CONSULTING ARCHITECT, A.I.A.

BURSON AND WILLIAMS ARCHITECTS INC.

SHOWBIZ PIZZA

APPROVED:

PRESIDENT

V.P. CONSTRUCTION

FOR PERMIT & BID

FOR CONSTRUCTION

REVISIONS:

#1

#2

SHOWBIZ PIZZA #605 – SAVANNAH

6700 ABERCORN ST. – SAVANNAH, GEORGIA

SHOWBIZ PIZZA TIME, INC.
4441 WEST AIRPORT FREEWAY
IRVING, TEXAS 75062

COUNTERS AND DETAILS

Date
08 FEB 1991

Revisions

Project Number
90-500

Sheet Number
A6

of 8



13 SECTION @ ORDER COUNTER

SCALE: 1" = 1'-0"



12 SALAD BAR ELEVATION – SIDE

SCALE: 3/4" = 1'-0"



11 SALAD BAR ELEVATION – BACK

SCALE: 1/4" = 1'-0"



SECTION AT BEER BOX AND TAPS



09 BEER BOX

NO SCALE



10 BUBBLE AWNING GUIDELINES

NO SCALE

BUBBLE AWNING

INSTALLATION INSTRUCTIONS:

1. Connect frame at x's, using self tapping screws provided.
2. Mount frame to wall at proper height using 2-1/2" woodscrews if going in wood. If going in concrete, use 2-1/2" lagscrews with lead anchors.
3. Lay canvas on frame with pocket toward frame, loosen screws on wall to enable canvas to side between wall and frame, re-tighten screws.
4. Pull canvas tightly on all four corners. Start lacing from corners go toward center.
5. After canvas is laced to frame check for wrinkles, replace if necessary.
6. Using small red bars attach outside top of frame through canvas with self tapping screws, then mount to building's overhang making sure front of canopy is straight, if not move red bars either in or out on overhand.



08 OUTSIDE WINDOW AWNING GUIDELINES

NO SCALE

OUTSIDE WINDOW AWNING

INSTALLATION INSTRUCTIONS:

1. Connect frame together at x's using self tapping screws provided.
2. Determine height of awning over window using chalk line, mark wall.
3. Fasten awning to wall using wood screws or lagscrews with lead anchors.
4. Take canvas sliding through slot, which is mounted on top of frame center canvas on frame, pull down front two corners.
5. Lace awning to frame, starting from corners working your way to the center. If awning has wrinkles, re-lace pulling canvas tightly.
6. Using projection bars provided, mount to frame at pocket and to window frame, cutting bar to right length to make awning level.



NOTE:
ONE LAYER 5/8" TYPE 'X' GYPSUM WALLBOARD APPLIED TO EACH SIDE OF 3 5/8" METAL STUDS AT 16" O.C. TO VERTICAL EDGES AND 12" O.C. TO INTERMEDIATE STUDS. STAGGER JOINTS 16" O.C. EACH SIDE. TYPICAL FOR ALL NEW FULL AND HALF WALLS.

05 TYPICAL HALF-WALL

SCALE: 3/4" = 1'-0"



06 COTTON CANDY MOUNT

SCALE: 1/2" = 1'-0"



NOTE:
LAMINATE CADDY CABINET WITH 5050R NAVAJO RED

G.C. TO INSTALL CADDY CABINET UNDER GLASS SHELVES IN GIFT AREA.

CADDY CABINET TO BE: 6'-0" LONG

07 CADDY CABINET

SCALE: 1" = 1'-0"

INSIDE AWNING WALL MOUNTED INSTRUCTIONS:

1. Connect frame using self tapping screws provided in frame.
2. Lifting ceiling panels, find wall studs, mark on outside wall on each stud center.
3. Slide canvas through slot mounted on top of frame. Raise canvas and frame to wall height.
4. Using conduit straps, put straps on head bar of awning at wall stud marks. Secure to stud using dry wall screws and washers.
5. Pull canvas tightly on frame.
6. Tie canvas to frame, starting at corners working way to center. If wrinkles develop, re-tie, pulling canvas tightly.

INSIDE AWNING CEILING MOUNT INSTALLATION INSTRUCTIONS:

1. Connect frames using self tapping screws provided in frame. Determine corner points on ceiling. Mount frame to ceiling using rigid conduit straps, with dry wall screws to ceiling grids. Using 1/2" EMT, cut 1/2" spacers to go between straps and ceiling grid if ceiling comes below grid work.
2. Slide canvas through slot, which is mounted on top of awning. Pull corners tightly. Starting at corner, tie to center. After canvas is tied, check for wrinkles. Re-tie with dry wall anchors if stud is not available.

NOTES:

1. When tieing, pull on canvas not on grommets. Grommets may pull out.
2. Always make sure canvas is centered on frame before tieing.

AWNING HARDWARE:

5/16 X 2" Woodscrews for exterior awning.

6" X 1-1/4" Drywall screws for interior awning.

3/16" flat washers to be used with all screws

Conduit straps for interior frames

1/2" Conduit spacers to use with conduit straps if ceiling panels come below ceiling grid work.

White drywall anchors to be used with conduit straps on end of awnings if studs are not available.

Lead anchors for exterior awnings if going in anything other than wood.





GENERAL SPECIFICATIONS FOR STEEL FRAMEWORK:

Welded Frames:

1. (a) The rib spacing for all bubbles, extended bubble and domes will be 15".
   (b) The horizontal members (projections) will be spaced 7' to 10'.
2. The frames will be made of EMT galvanized thin wall steel tubing 1/2" – 3/4" – 1-1/4" O.D.
3. The frames will be MIG welded.
4. (a) All welds will be wire brushed and ground to have a smooth finish.
   (b) All welds will be painted with Galvan or equal.



01 WALL FRAMES

SCALE: 1" = 1'-0"



02 GIFT AREA SHELVING

SCALE: 1 1/2" = 1'-0"



03 BENCH BUMPER DETAIL

NO SCALE



04 INTERIOR AWNING GUIDELINES

SCALE: 3/4" = 1'-0"

JACK E. BUDSON, CONSULTING ARCHITECT, A.I.A.
B&W
BUDSON AND WILLIAMS
ARCHITECTS INC.

SHOWBIZ PIZZA

APPROVED:

PRESIDENT

V.P. CONSTRUCTION

FOR PERMIT & BID:

FOR CONSTRUCTION:

REVISIONS:

#1

#2

SHOWBIZ PIZZA #605 – SAVANNAH

6700 ABERCORN ST. – SAVANNAH, GEORGIA

SHOWBIZ PIZZA TIME, INC.
4441 WEST AIRPORT FREEWAY
IRVING, TEXAS 75062

NOTES AND DETAILS

Date
08 FEB 1991

Revisions

Project Number
90-500

Sheet Number
A7

of 8

GENERAL CONTRACTOR NOTES

1. Verify OWNER FURNISHED items with Project Manager prior to construction. General Contractor to be responsible for unloading of Owner Provided items from Owner's trailer.
2. Verify all HEALTH DEPARTMENT REQUIREMENTS are met during remodel.
3. Project Manager will determine whether counters, fixtures and other assets will be kept or disposed of by contractor.
4. Field verify all measurements, dimensions, elevations and conditions prior to construction.
5. All dimensions are to take precedence over scale. Dimensions on plans, elevations, sections and details.
6. G.C. to hang menu board, employee plaques, and all signs with pan head screws. Neon to be installed by owner.
7. Not used.
8. Sprinkler system to be lowered or raised to new ceiling height in all areas where needed. G.C. to use licensed fire sprinkler company. Company to provide owner with plan after completion.
9. Sprinkler company to supply five extra heads and wrench (fire wrench to remain in sprinkler closet).
10. Not used.
11. Re-install to remount air diffusers and return air grills after any work on ceiling.
12. All new full walls and half walls must have vinyl base to match existing base.
13. All walls and ceilings of food areas must be smooth, easily cleanable and light in color.
14. Any exposed sheetrock edges to have J mold.
15. All trim must extend to end of walls, doors, etc. (trim to match existing).
16. Provide and install 1/4" red oak chair rail on all walls.
17. Provide flag and flagpole.
18. Attach to be installed with Robertson screws.
19. Re-paint room to [illegible] & [illegible].
20. Install [illegible] drug safes and cash drawers, in new order counter.
21. Provide and install mirrors with full coverage mastic. Caulk mirror and wall with.
22. Add trips to any door waived on under Scope of Work.
23. Run water line for Coke machine.
24. Run water line to carbonator, filtrator & coke machine in beverage area.
25. Run water line to tea maker - kitchen next to pick up window.
26. Use PVC behind beverage area, match existing. See detail.
27. Caulk table splash sides, beverage bar top, bottom & sides.
28. Provide and install aluminum inner guards on new beverage bar. See detail.
29. All solid bars but not type food service and other self serve food shall be shielded so as to intercept a direct line between the customer's mouth and the food being displayed, by the proper overhang of the sneeze guard. Verify with Health Department regulations.
30. Re-mount point of sale (POS) terminal (2) above make table. Alternate ring from existing or mounted on make table.
31. Run wire concealed in wall to valved termination at "B" wear Roller", Raymouth & Whip. A Demon locations. Use 1" PVC schedule 40.
32. Provide and install in line ball valves on all plumbing changes or additions.
33. Cut hole opening through wall for slim line beer cabinet. Ref Sheet A7. Rear box installation by General Contractor. Purchase and install stainless steel cover for unused dispenser opening in beer box and seal.
34. FINAL CONTRACTOR TO PROVIDE ONE (1) SET OF ACCURATE AS BUILT DRAWINGS TO OWNER (OWNER REQUIREMENT % WITH OWNER).
35. Provide and install 3/4" drain line run from spindl pan to existing floor drain (sink). Provide 1 1/2" gap between spindl pan and floor sink(sink). (See Note 62 also for full note).
36. Install to remount guest check holder to bottom of portion chart.
37. Remove pass thru shelf. Patch wall to match existing finish.
38. G.C. to install existing glass mirror behind order counter prior to sitting counter in place. Field verify. Mirror is on site.
39. If mirror is available, install wheels at under counter refrigerator and install behind order counter prior to sitting counter in place. Wires to remain on unit.
40. A wood trim to be natural color.
41. All light bulbs will be re installed each day.
42. Caulk all splashes and joints.
43. All outlet covers must be replaced each day.
44. All outer doors, new and existing, must be self closing and tight fitting.
45. Replace fire extinguishers where required. Replace if indicated. Relocate fire alarm where needed. G.C. to use a licensed fire alarm company. Telephone.
46. Replace any broken or missing quarry tile and quarry base. Put quarry tile base on back of self serve beverage kitchen side. Match existing.
47. Remove dimmer boxes, patch walls where dimmers and switches are removed.
48. Remove two (2) "KIDS APPROVAL" signs in kiddie area.
49. Carpet Space Station (Ref. Dwg. Chalk steps.
50. Rip carpet from front to back of building.
51. Provide and install 2 x 4 grex on ceiling tile over Hung Shot. Screw to grid with six screws and spacers. Install plex paralin to hung shot.
52. Hang 5 x 5 Coke umbrellas randomly, not in pattern, in kiddie area where light does not shine on them.
53. Provide and install 1/2" Marlite corner molds on all hallway corners.
54. Install 1" x 1" x 1/4" metal angle brace or 2"aa pipe at all hallway openings over both sides of hallway with Marlite 5407 Butt [illegible] UNLESS OTHERWISE NOTED ON ELEVATIONS.
55. Remove 21 bulbs where required.
56. Install new 110 floor for floor receptacles, with a electric power wet box. Ref. height of slab.
57. Remove existing men and women signs on restroom doors. Install new signs in same location on restroom doors.
58. Reuse all copper tubing which penetrates walls.
59. Not used.
60. Put plastic down under any saw being used in store.
61. Aluminum beverage corner guards to be installed above base.
62. General Contractor to remove wall vinyl before painter textures and paints.
63. General Contractor to install solid bar top to fit existing spindl pan/sink.
64. General Contractor to assemble and install owner provided park benches.
65. General Contractor to assemble table tops and bases and set booths and tables in place.
66. General Contractor to provide and install aluminum track, #A3752 (800 lb lbs) with rubber under #7 1/4 reg 1776-0109 where [illegible] vinyl and is quality.
67. General Contractor to require carpet layer to use seam sealer on carpet seams.
68. General Contractor to install diaper changing shelf provided by the owner in the women's restroom.
69. General Contractor to install transition strips at all flooring changes.

RESPONSIBILITY CHART

DESCRIPTION	PROVIDED BY	INSTALLED BY
INTERIOR AWNINGS	OWNER	G.C.
WALL PORTRAITS	OWNER	G.C.
MURALS	OWNER	G.C.
VINYL CHECKS 179 LINEAR FEET	OWNER	G.C.
UMBRELLAS	OWNER	G.C.
PLANTS	OWNER	G.C.
CURTAINS	OWNER	G.C.
SPEAKER CLOTH	OWNER	G.C.
EXTERIOR SIGNAGE	OWNER	OTHER
INTERIOR NEON	OWNER	OTHER
BASE NEON PACKAGE(S)	OWNER	G.C.
MENU BOARD	OWNER	G.C.
MENU SLATS	OWNER	OTHER
SIGNAGE	OWNER	
COIN CHANGER	OWNER	G.C.
BATTER UP	OWNER	G.C.
MEN/WOMEN	OWNER	G.C.
OCCUPANCY	OWNER	G.C.
CONST. POSTERS	OWNER	OWNER
ROLLER BOWLER SIGN	OWNER	G.C.
SKEEBALLS SIGN	OWNER	OWNER
MIRRORS	G.C.	G.C.
GLASS SHELVES	G.C.	G.C.
SHELVES	G.C.	G.C.
WINDOWS	G.C.	G.C.
STAIR NOSING	G.C.	G.C.
WATCH YOUR STEP SIGN	OWNER	G.C.
OPERATIONS SIGN	OWNER	G.C.
RESTROOMS SIGNS	OWNER	G.C.
ELECTRICAL MATERIALS		G.C.
HANGING LIGHTS	OWNER	G.C.
LIGHT INSERTS	OWNER	G.C.
LAMPS	G.C.	G.C.
INCANDESCENT FIXTURES	G.C.	G.C.
FLUORESCENT FIXTURES	G.C.	G.C.
FLOORING & OTHER MATERIALS		G.C.
CARPET 6,488 SQUARE FEET	OWNER	G.C.
TILE	G.C.	G.C.
VINYL CROSSWALK	OWNER	G.C.
CABINET/COUNTERS	OWNER	G.C.
GIFT CADDY	OWNER	G.C.
DROP BOXES	OWNER	G.C.
SALAD BAR/SNEEZE G	OWNER	G.C.
CONDIMENT BAR	OWNER	G.C.
CHROME TUBES	OWNER	G.C.
THANK YOU BOXES	OWNER	G.C.
HOSTESS STAND	OWNER	G.C.
COAT RACKS	OWNER	G.C.
BOOTH INSERTS	OWNER	G.C.
STAINLESS BEVERAGE CENTER	OWNER	G.C.
BEER SYSTEM	OWNER	G.C.
DRAIN PAN	OWNER	G.C.
COKE DISPENSER	OWNER	G.C.
ICE MACHINE	OWNER	G.C.
REFRIGERATOR	OWNER	G.C.
COFFEE/TEA DISPENSER	OWNER	G.C.
SALAD PAN	OWNER	G.C.
CUP DISPENSER	OWNER	G.C.
LID DISPENSER	OWNER	G.C.
TRASH LINERS	OWNER	G.C.
SECURITY SYSTEM(REPAIR IF REQD)	EXISTING	G.C.
BOOTHS	OWNER	G.C.
BENCHES(INTERIOR)	OWNER	G.C.
BENCHES(EXTERIOR)	OWNER/G.C.	G.C.
TABLES	OWNER	G.C.
BASES	OWNER	G.C.
UPHOLSTERY	G.C.	G.C.
EXTERIOR AWNINGS	OWNER	G.C.
DOOR HARDWARE	G.C.	G.C.
INTERIOR DOORS	G.C.	G.C.
FRONT DOORS	G.C.	G.C.
VINYL BASE	G.C.	G.C.
QUARRY TILE	G.C.	G.C.
QUARRY BASE	G.C.	G.C.
MARLITE	G.C.	G.C.
OAK TRIM	G.C.	G.C.
BABY CHANGING AREA	OWNER	G.C.
PIZZA PAN DISPLAY SET	OWNER	G.C.

GENERAL PAINTING NOTES

1. Provide plastic to cover items not being painted.
2. Spray ceiling mounted and recessed speakers with hi-gloss white enamel.
3. Hand paint ceiling projector, light bars and vents. DO NOT paint instruction plate on back of the projector.
4. Remove all ceiling clips prior to painting ceiling.
5. Paint ceiling tile and grid P-11 in all public areas.
6. Paint ceiling over filled before painting.
7. Clean and paint all ceiling diffusers in public areas, and reinstall.
8. All items taped, covered up or removed, must be returned to operating condition each changer surfaces to have Penetrol added to paint.
9. Use quick drying mud for joints and texture.
10. All trim to be sanded and sealed all four sides.
11. Remove all pictures, clean and reinstall after painting doors. Do not paint gasket on door windows.
12. Paint and seal front doors before installation.
13. All cracks are filled before painting.
14. Paint sides of ball crow steps P-2.
15. Spray coin changers with White Epoxy Glidethane - 4550. All painted games or coin changer surfaces to have Penetrol added to paint.
16. Spray brown table bases flat black, if needed.

EXTERIOR PAINTING NOTES

1. Paint exterior of building except for brick and brick trim as specified on plans. Reinstall any loose boards on parapet before painting.
2. Paint any exterior electrical panels, conduits and gas piping P-6.
3. Paint exterior swing hangers, if needed.
4. Paint exterior wall hydrant box P-6, only if it is not brass.
5. Paint "NOW APPEARING" boxes P-12, making sure the words NOW APPEARING is painted out.
6. Drop cloths are to be used wherever painting is being done.
7. There are to be NO ALTERNATES to paint schedule.

PAINT SCHEDULE

KEY	NAME	BASE	FORMULA
P-1	GLIDDEN INTERMEZZO - Interior Walls Semi-gloss	3718	YOX-6, LY-2, BLK-2
P-1A	GLIDDEN INTERMEZZO - Semi-gloss	4618	YOX-6, LY-2, BLK-2
P-2	GLIDDEN 80-18 Interior Blue Semi-gloss	4699	TBL-8P, VO-2P, BLK-24, W-32
P-3	GLIDDEN GREEN - Restroom Semi-gloss	4580	NP-1P44, TGR-6P50, TBL-8.
P-4	GLIDDEN SAFETY RED - Front Door Exterior Checkerboards High-gloss	4520	
P-5	GLIDDEN IMPERIAL BLUE - Exterior Checkerboards High-gloss	4564	
P-6	GLIDDEN SWEDISH SNOW ENAMEL Exterior Walls - Semi-gloss	39-9	DXR-1
P-7	GLIDDEN POLYURETHANE - Satin Finish - Front Door Satin Finish - Interior		
P-8	LACQUER SAND AND SEAL - Natural Finish Semi-gloss		
P-9	GLIDDEN GREEN - Exterior Checkerboards High-gloss	4580	YEG-5P-16 TGR-2P-48 NT-12
P-10	GLIDDEN GOLD - Exterior Checkerboards High-gloss	4580	RO-1P-36 YL-9P-24
P-11	GLIDDEN ACOUSTIC WHITE - Ceiling Tile - Flat White	5070	RO-1, NT-3
P-12	GLIDDEN GREEN - New Appearing Boxes High-gloss	4580	LY-3P50, TGR-5P26, BLK-2P58

TOKEN CHANGE MACHINE - GLIDDEN WHITE EPOXY GLIDETHANE - 4550

DEMOLITION NOTES

1. Prior to demolition, contractor will cover and protect all chairs, tables, fixtures, ALL GAMES, and rides.
2. Prior to sawcutting floor (wet saw only). Contractor will verify game layout.
3. Contractor will provide a minimum 30 CU dumpster at location during demolition.
4. Demolition schedule to be approved by Project Manager prior to start.
5. Patch and refinish walls and floors at all "demoed" wall locations.
6. Install new grid and ceiling tile when walls have been removed.
7. Remove power poles.
8. Remove all panels over the dimmers, show controls, etc. and patch wall. Finish to match existing.
9. Remove monitor shelves, and store monitors at location.
10. All remodeled walls, ceilings and floors of food preparation and storage areas must be smooth, non-absorbent, easy to clean and light colored.
11. Patch holes on wall where shelves are removed.
12. Relocate Everpure filter system to new COKE water system, if needed.
13. Relocate fire extinguishers where necessary.
14. Floor stone floor where needed.
15. Remove clips on ceiling before ceiling is painted.
16. All existing floor drains, floor sinks and cleanouts to remain unless otherwise noted.
17. Remove any existing wainscoting, paneling, carpet, sound board & trim on walls. Repair and refinish walls.
18. All plumbing in remodeled areas not used should be disconnected, capped and floor leveled. New finishes to match existing.

TABLE SCHEDULE

LOCATION	SIZE	No.	REMARKS
SHOWROOM	42" x 30"	27	EXISTING
	60" x 30"	7	EXISTING
	30" x 48"	19	NEW WITH BASE
SKILLS	48" x 30"	4	NEW WITH BASE
KIDDIE	48" x 30"	2	NEW WITH BASE
	40" x 40"	1	NEW WITH BASE
	60" X 30"	5	NEW WITH BASE

BOOTHS SCHEDULE

LOCATION	SIZE	No.	REMARKS
SHOWROOM	60" SINGLE	2	EXISTING
	60" DOUBLE	6	EXISTING
	48" SINGLE	7	NEW
	48" DOUBLE	15	NEW
SKILLS	48" SINGLE	2	NEW
	48" DOUBLE	3	NEW
KIDDIE	48" SINGLE	2	NEW
	48" DOUBLE	1	NEW
	3/4 BOOTH	1	NEW48"X84"x90"X60"
	60" SINGLE	2	NEW
	60" DOUBLE	4	NEW

109	CHAIRS	34	NEW BASES
		1	NEW 1 LEG BASES

DOOR HARDWARE SCHEDULE

HARDWARE SET #1 DOOR D-1
3'-0" x 7'-0 x 1-3/4" (Type "A").
18 ga. Hollow Metal Door & 16 ga. Frame

LCN	Closer 4040 SNB, US3 Finish
HAGER	Butts (3) per door, BB-1279 4.5" x 4.5" NRP, US3
HAGER	Flush Bolts #282D on inside, US3 Finish
SCHLAGE	Deadbolt (1) #B-460P with inside thumb, US3
HAGER	Kick Plates (2) 8" x 34" inside & Outside - US3
HAGER	Push Plates (2) #300, 3.5" x 15" US3
HAGER	Pull Plates (2) #400 3.5" x 15" US3
BALDWIN	Silencers (6) #4035
VON DUPRIN	Touch Bar 99 Series 9975-F US3 Finish
NAT. GUARD	Threshold #425EV Alum. Gold Anodized
NAT. GUARD	Astragal #140PB 2-7/ Alum. Gold Anodized
NAT. GUARD	Weatherstrip #180AV 20' Alum. Gold Anodized
HAGER	Floor Stop #282F with riser as required, US3

HARDWARE SET #2 DOORS D-2 & D-3
2'-6" x 6'-8" x 1-3/4 (Type "B")
W/10" x 10" Clear Glass Insert.
Solid Core Door W/Hollow Metal Frame.

STANLEY	Butts BW179 26D 4.5" x 4.5" (Two Pair)
CIPCO	Push Plate 550K-630
CIPCO	Pull Plate 550K x 43-630
LCN	Closer 1560
CIPCO	Kick Plate 5153 30" x 34"
IVES	Stop (1) 436 B26D



TYPE "A" TYPE "B"

ELECTRICAL NOTES

1. Remove lights in existing sneeze guard.
2. Replace any missing baffles.
3. Remove outlets, conduit and switches from any wall to be demolished.
4. Make certain all outlets work.
5. Install six (6) or seven (7) ceiling outlets for neon transformers. Verify on Power Plan. Neon Installation by Owner.
6. Remove all dimmers and light switches except in showroom.
7. Relocate all emergency lights, security equipment and exit lights if necessary.
8. All light bulbs will be reinstalled each day.
9. All outlet covers must be replaced each day.
10. Remove power poles.
11. Relocate thermostats if and where necessary.
12. Reinstall all smoke detectors.
13. Label all panel breakers.
14. Shield all lights in food handling areas and provide 50 foot candles in light on all work surfaces.
15. On FIRST night check emergency and exit lights.
16. Check security system.
17. Paint all rim on fixtures.
18. Repair or replace all exit lights, if necessary.
19. Receptacles and plates to be ivory ● Buff Marlite & P-1, brown ● Oak Marlite.
20. Relocate security pad if necessary. Verify with Project Manager.
21. Check outdoor lighting and sign override to make sure they are working.
22. Install owner provided inserts in all incandescents during re-lamping.
23. Replace any existing broken outlet covers.
24. Outlet on front of stage to be brown.
25. Provide and install two four foot (4') fluorescent tubes for sneeze guard. Install prior to hanging sneeze guard.
26. Provide and install two two-foot (2') fluorescent tubes for gift counter. Refer to lighting schedule.
27. Registers and printer require an isolated grounded receptacle on dedicated circuit.
28. Showroom hanging lights bottom of globe 5' 0" AFF.
29. Run flex in chrome tube through top of sneeze guard then to sneeze guard light.
30. Remove corridor fluorescents. Replace with incandescents. Refer E2.
31. Re-install contacts on all exterior doors after any work on those doors.
32. Verify that ceiling speakers in remodeled areas are in proper working order after ceiling & electrical work is complete.
33. Verify that the alarm system is in proper working order after ceiling & electrical work is complete.
34. Provide and install outlet above ceiling for all neon. Run all necessary wiring.

LIGHT BULB SCHEDULE

FIXTURE	LOCATION	No.	VOLTS	LAMPS
B, C & P	SKILLS/KIDDIE/ CORRIDOR	87	120 V.	1: 150 W. A-21 WHITE.
B & C	SHOWROOM	31	120 V.	1: 100 W. A-21, SYLVANIA SOFT PINK.
K	SHOWROOM.	14	120 V.	1:60 W. A-19, SYLVANIA SOFT PINK.
L & N	CORRIDOR	17	120 V.	1: 90 W. PAR-38 FLOOD.

LIGHTING SCHEDULE

KEY	DESCRIPTION	No.	NOTES	MFG.
A	RECESSED INCANDESCENT TO BE RELOCATED	51		EXISTING
B	FIXTURE TYPE "A" MOVED TO NEW LOCATION	51	WITH OMEGA YPS-6E REFLECTOR INSERT	EXISTING VERIFY
C	FIXTURE TYPE "A" TO REMAIN AT LOCATION	62	WITH OMEGA YPS-6E REFLECTOR INSERT	EXISTING TO TO REMAIN
D	2 LB 2408 FIXTURE WITH F40 T12CW PROVIDED BY ELECTRICAL CONTRACTOR	2	BEVERAGE	LITHONIA
E	C 140 FIXTURE SPX35 F40, SUH ENERGY SAVING BALLAST SUPER LOW HEAT WITH TUBE GUARD PROVIDED BY ELECTRICAL CONTRACTOR	2	SNEEZE GUARD USE SYLVANIA F40 GRO-LUX LAMP (F40GRO)	LITHONIA
F	C 120 FIXTURE SPX35 F20, SUH ENERGY SAVING BALLAST SUPER LOW HEAT WITH TUBE GUARD PROVIDED BY ELECTRICAL CONTRACTOR	2	SNEEZE GUARD USE SYLVANIA F20 GRO-LUX LAMP (F20T12GRO)	LITHONIA
H	S 130 FIXTURE WITH F30 T12 CW PROVIDED BY ELECTRICAL CONTRACTOR	2	GIFT COUNTER (1 PER CASE)	LITHONIA
K	HANGING LIGHT 3074-06 PB WHT 17" CHROME PROVIDED BY OWNER	14	SHOWROOM	PARK ROW LIGHTING
L	150 WR-40 HOUSING 1202 TRIM 1222 PROVIDED BY ELECTRICAL CONTRACTOR	8	EYEBALL	LIGHTOLIER
M	RECESSED EYEBALL FIXTURE TO BE RELOCATED	9	WITH OMEGA YPS-6E REFLECTOR INSERT	EXISTING
N	FIXTURE TYPE "M" MOVED TO NEW LOCATION	9	WITH OMEGA YPS-6E REFLECTOR INSERT	EXISTING
P	RECESSED INCANDESCENT AT NEW LOCATION PROVIDED BY ELECTRICAL CONTRACTOR	11	WITH OMEGA YPS-6E REFLECTOR INSERT	NEW - MATCH FIXTURE TYPE "A"

RELAMP ALL LIGHTS UNDER SCOPE OF WORK. SHOWROOM WITH PINK BULBS AND ALL OTHER AREAS WITH WHITE BULBS. SEE LIGHT BULB SCHEDULE. ELECTRICIAN TO INSTALL OWNER PROVIDED OMEGA INSERTS IN ALL INCANDESCENTS DURING RELAMPING.

JACK K. MITCHAM, CONSULTING ARCHITECT, A.I.A.
BSW HUDSON AND WILLIAMS ARCHITECTS INC.

SHOWBIZ PIZZA
APPROVED
PRESIDENT
V.P. CONSTRUCTION
FOR PERMIT & BID
FOR CONSTRUCTION
REVISIONS:
#1
#2

SHOWBIZ PIZZA #605 - SAVANNAH
6700 ABERCORN ST. - SAVANNAH, GEORGIA

SHOWBIZ PIZZA TIME, INC.
4441 WEST AIRPORT FREEWAY
IRVING, TEXAS 75062

NOTES AND SCHEDULES

Date
08 FEB 1991

Revisions

Project Number
90-500

Sheet Number
A8
of 8

POSTERS/PORTRAITS SCHEDULE:

FAIRY POSTERS (9)
GENERAL CONTRACTOR IS TO INSTALL FAIRY POSTERS PROVIDED BY OWNER
1 PP DALI TO THE FUTURE
2 PP BAT MUNCH
3 PP BEAGLE JUICE
4 PP GONE WITH THE WING
5 PP INDIANA JONES
6 PP WIZARD OF CHEESE
7 PP JAWS
8 PP CLOSE ENCOUNTERS OF THE BIRD KIND
9 PP CROCODILE CHASE E

WALL PORTRAITS (5)
GENERAL CONTRACTOR IS TO INSTALL WALL PORTRAITS PROVIDED BY OWNER
1 WP CHUCK E CHEESE
2 WP BAT MUNCH
3 WP JASPER T. JONES
4 WP HELEN KENNY
5 WP PASQUALI'S

GENERAL CONTRACTOR IS TO PROVIDE AND INSTALL (2) WOOD BAR FRAMES - REFER TO A7/03

GENERAL CONTRACTOR IS TO INSTALL WALL MURALS PROVIDED BY OWNER AS INDICATED ON DRAWING

NOTE:

1. MONITOR REGISTER OUTLETS
   A) ISOLATED OUTLETS AT ORDER COUNTER GROUNDED DEDICATED CIRCUIT
   1) STANDARD OUTLET FOR GLASS CHILLER - 7 AMPS SINGLE PHASE AT ORDER COUNTER
   2) 4-PLEX OUTLET & TELEPHONE JACK FOR CREDIT CARD MACHINE
2. REMOVE ALL YELLOW CEILING LIGHTS
3. INSTALL EYEBALL SPOTS AIMED ON AWNINGS REFER SHEET E-2
4. REPLACE ANY EXISTING BROKEN OUTLET COVERS
5. REMOVE CORRIDOR FLUORESCENTS REPLACE WITH INCANDESCENTS REFER SHEET E-2
6. WE INSTALL CONTACTS ON ALL DOORS AFTER ANY WORK ON DOORS
7. VERIFY THAT CONTACTS ARE IN WORKING ORDER
8. VERIFY THAT CEILING SPEAKERS IN REMODELED AREAS ARE IN PROPER WORKING OR - AFTER CEILING/ELECTRICAL WORK IS COMPLETE
9. VERIFY THAT THE ALARM SYSTEM IS IN PROPER WORKING ORDER AFTER CEILING/ELECTRICAL WORK IS COMPLETE
10. PROVIDE AND INSTALL SNEEZE GUARD AMP TRUSS - HANGING UNDER GUARD RUN FLEX-N-GROW TUBE THRU TOP OF UNITS - AND LIGHT
11. RELOCATE ALL EXISTING ELECTRICAL DEVICES AND OUTLETS ON WALLS THAT MOVE
12. ALL ELECTRICAL WORK SHALL CONFORM TO LOCAL CODE REQUIREMENTS
13. ALL NEON SIGNS TO BE ON DEDICATED CIRCUITS

LEGEND

- NEW DUPLEX OUTLET
- NEW DEDICATED OUTLET
- NEW 4-PLEX OUTLET
- EXISTING OUTLET (VERIFY)
- NEW FLOOR OUTLET

NOTE: IT IS THE CONTRACTORS RESPONSIBILITY TO FIELD VERIFY THE LOCATION AND OPERATION OF ALL EXISTING ELECTRICAL OUTLETS - REUSE IF POSSIBLE



TOTAL SEATING: 273 PEOPLE

01 ELECTRICAL, GAMES AND SEATING PLAN

SCALE: 3/16"=1'-0"

JACK R. BURSON, CONSULTING ARCHITECT, A.I.A.

BURSON AND WILLIAMS ARCHITECTS INC.

SHOWBIZ

APPROVED:
PRESIDENT:
V.P. CONSTRUCTION:
FOR PERMIT & BID:
FOR CONSTRUCTION:
REVISIONS:
#1
#2

SHOWBIZ PIZZA #605 - SAVANNAH
6700 ABERCORN ST. - SAVANNAH, GEORGIA

SHOWBIZ PIZZA TIME, INC.
4441 WEST AIRPORT FREEWAY
IRVING, TEXAS 75062

ELECTRICAL, GAMES AND SEATING PLAN

Date: 08 FEB 1991

Revisions:

Project Number: 90-500

Sheet Number: E1

of 2

RECEIVED APR 11 1991 EST. OF INSPECTIONS

GENERAL NOTES:

1. REWORK EXISTING SPRINKLER SYSTEM IN ALL AREAS WHERE CEILING WORK IS TO BE DONE TO BE FLUSH WITH CEILING AND TO COMPLY WITH ALL LOCAL CODE REQUIREMENTS.
2. ALL EXISTING SUPPLY AND RETURN AIR GRILLES TO REMAIN UNLESS OTHERWISE NOTED.
3. RELOCATE ALL MECHANICAL GRILLES IN AREAS WHERE CEILING WORK IS TO BE DONE TO APPROXIMATELY THE SAME LOCATION IN THE NEW CEILING GRID.
4. ALL EXISTING LIGHTING TO REMAIN UNLESS OTHERWISE NOTED.
5. RELOCATE ALL LIGHTS AND MECHANICAL GRILLES IN KITCHEN, STORAGE, AND OFFICE AREAS ADJACENT TO NEW CONSTRUCTION AREAS AS REQUIRED.
6. RELOCATE EMERGENCY AND EXIT LIGHTING AS REQUIRED BY NEW CONSTRUCTION TO CONFORM TO ALL LOCAL CODE REQUIREMENTS.
7. ALL EXISTING RETURN AIR GRILLES TO REMAIN IN EXISTING LOCATIONS.
8. ALL NEW BALLS THAT ARE IN EXISTING CEILINGS ARE TO BE FRAMED WITH SUSPENDED EDGE GRID SYSTEM.
9. GENERAL CONTRACTOR IS TO PROVIDE AN ALTERNATE BID FOR PAINTING CEILING IN ALL AREAS AS ALREADY SHOWN TO BE PAINTED ON DRAWINGS WITH THE EXCEPTION OF RESTROOMS.

KEY

- RECESSED INCANDESCENT LIGHT
- RECESSED EYEBALL LIGHT
- CEILING MOUNTED INCANDESCENT LIGHT
- HANGING INCANDESCENT LIGHT
- LAY-IN FLUORESCENT LIGHT
- SUPPLY AIR GRILLE
- RETURN AIR GRILLE
- EMERGENCY LIGHT



01 REFLECTED CEILING PLAN

SCALE: 3/16" = 1'-0"

OFFICE COPY

JACK W. BURGAN, CONSULTING ARCHITECT, A.I.A.

B&W BURGAN & WILLIAMS ARCHITECTS INC.

SHOWBIZ PIZZA

APPROVED:

PRESIDENT

V.P. CONSTRUCTION

FOR PERMIT & BID:

FOR CONSTRUCTION:

REVISIONS:

#1

#2

SHOWBIZ PIZZA #605 - SAVANNAH

6700 ABERCORN ST. - SAVANNAH, GEORGIA

SHOWBIZ PIZZA TIME, INC.
4441 WEST AIRPORT FREEWAY
IRVING, TEXAS 75062

REFLECTED CEILING PLAN

Date: 08 FEB 1991

Revisions

Project Number: 90-500

Sheet Number: E2

of 2